

Hope Creek Circulating Water Pipeline 2013 Carbon Fiber Upgrade

Jim Mechionna

Corporate Program Manager- Engineering Services, Piping
PSEG Nuclear Salem and Hope Creek Generating Stations
James.melchionna@pseg.com

Anna Pridmore, PhD

Vice President- Pipeline Solutions
STRUCTURAL TECHNOLOGIES
apridmore@structural.net
714-869-8824

Background- Hope Creek Generating Station



- Located in Salem, NJ
- Station consists of 1,268 MW boiling water reactor (BWR)
- Circulating Water System consists of 144in PCCP
- Pipelines have been inspected for the past 8 years and distressed pipes have been identified

Background- PCCP Deterioration

- Cracking of Outer Mortar
- Corrosion or Embrittlement of Wires
- **Wires Break**
- Mortar Coating Delaminates
- Concrete Core Delaminates
- Core Cracks
- Failure



Background- Project Details

Project Scope:

- Carbon fiber reinforced polymer (CFRP) composite lining of seven (7) sections of 144-in PCCP during the October 2013 outage

Unique Project Challenges:

- Removal of muck and construction of access through cooling tower basin
- Single point of entry to complete all in-pipe activities
- Construction of 2-tiered access within the 144-inch diameter pipeline
- Changes in elevation and slope conditions within scope area
- Removal of a pre-existing carbon fiber system

QA/QC Program:

- 3rd party Quality Control inspector
- Full time Quality Assurance manager
- Multiple owner representatives

Background- Quality Control Program

Project: 130266-RP18: Hope Creek, CFRP Lining of Line A
 Inspector: Anna Prohaska and team
 Dates of Construction: October 2013 referring outage
 Contractor: STRUCTURAL
 Installation Supervisors: Jan Dunn and Jason Alexander

Pipe No. A-122
 MH Location: Entry through Bypass Pipe Near Cooling Tower

I. QC SURFACE PREP (PRE CFRP INSTALLATION)

POCP Sounding/Cracks per PSEIG VTD 431878, Sec. 3.02	Show hollow sounds and cracking of the concrete core on diagram located on the back of this form.	Structural Initial	Date
		AP	10/21/2013

Installation Step	Comments	Structural Initial	Date
Concrete Surface Profile (CSP-3)	Minimum profile of CSP 3	AP	10/21/2013
Joint Preparation		AP	10/21/2013
Steel Surface Profile (SSP-10)	OK	AP	10/21/2013
Concrete Surface Temperature	OK	AP	10/21/2013
Cylinder Repairs?	none required	AP	10/21/2013
Surface Cleanliness	OK	AP	10/21/2013
Surface Dryness	OK	AP	10/21/2013

II. QC DURING CFRP INSTALLATION

Installed Layer	Hoop/Long	Date	Time	Inside Pipe			Mixing Area		Meets Spec?		
				Surface Temp (°F)	Air Temp. (°F)	RH (%)	Air Temp. (°F)	RH	Structural Initial	Date	
Primer	-	10/21/2013	19:20	55	55	57	52	55	51	AP	10/21/2013
CFRP/CFRP at Joint	L	10/21/2013	19:20	55	55	57	52	55	55	AP	10/21/2013
Layer 1	L	10/22/2013	12:00	76	60	43	54	70	44	AP	10/23/2013
Layer 2	L	10/22/2013	15:15	52	72	33	48	55	52	AP	10/23/2013
Layer 3	H	10/23/2013	14:00	76	70	42	54	57	42	AP	10/23/2013
Layer 4	H	10/23/2013	16:30	76	70	42	52	54	42	AP	10/23/2013
Layer 5	H	10/24/2013	12:40	75	71	33	44	51	54	AP	10/24/2013
Layer 6	H	10/24/2013	15:30	81	75	42	52	N/A (meets spec)		AP	10/24/2013
Layer 7	H	10/25/2013	10:16	76	75	48	36	47		AP	10/25/2013
Layer 8	H	10/25/2013	15:20	52	75	32	50	55	38	AP	10/25/2013
Top Coat	-	10/25/2013	14:00	56	57	43	55	50	35	AP	10/25/2013

Verify type and direction of flow, overlaps, seams, duration between layers, etc.

Expansion Ring Installation Meets Spec?

	Pressure (psi)	Structural Initial	Date
Upstream	N/A	AP	10/25/2013
Downstream	N/A	AP	10/25/2013

III. QC POST CFRP INSTALLATION

Delays/Bubbles - Offset measured from upstream looking downstream					Shore D Handhole		
Size	Offset	Clock	Addressed?	Layer	Date	Time	Readings
2in x 12in	35	9:30	reel	~400	10/27/2013	8:40	Top of Pipe: 75, 67, 55, 70, 80
20 x 30 in	35	9:30	reel	Layer 8S (Layer 8)	10/27/2013	9:20	Bottom of Pipe: 75, 80, 74, 74
					10/29/2013	11:00	Bottom of Pipe: 75, 75, 80, 87, 75

No. Areas Addressed? 2

Touch-Up Areas: 2 10/25/2013

Curing Temperature

Date	Time	Air Temp. (°F)	Relative Humidity (%)	Surface Temp (°F)	Structural Initial
10/27/2013	8:00	57	33	84	AP
10/28/2013	9:00	56	11	105	AP
10/29/2013	11:00	54	32	99	AP

See attached page for additional temperatures throughout cure.

Approval of Post Installation Inspection (Meets Spec / Meets Recom.)

Structural Approval	Date
Anna Prohaska	10/29/2013

Permitted Air Temp in Pipe and Time Cure Regimes	
Item #	Required Cure per ECI and PSEIG
1	80°F for a minimum of 48 hours
2	80°F for a minimum of 35 hours
3	110°F for a minimum of 12 hours

PSEIG Final Walk-through (see attached comments page for any notes):

Inspector	Date
Raouf Parnianpour	10/29/2013
Nina Parodi	10/29/2013
James Melchiorra	10/29/2013
Andrew Simons	10/29/2013
Eduardo Jagannathan	10/29/2013

Multiple QA/QC Personnel

- 3rd Party inspector
- Full time Quality Assurance Manager
- Multiple Owner Representatives

Documentation for each stage of implementation

- Material verification
- Surface preparation
- Mixing and saturation
- CFRP liner installation
- End details and special detailing
- Top coat
- Final cure

Unique Project Challenges



- Cooling water tower basin filled with muck
- De-mucking required prior to access into the pipeline
- Quantity of muck unknown prior to start of outage
- Specialty scaffolding required to bring materials and personnel from staging area into basin

Unique Project Challenges



- Materials, personnel, and ventilation equipment all routed through a single point of entry
- Main access to the circulating water pipe required navigation through a butterfly valve
- Substrate had buildup of existing epoxy (remainder of failed carbon fiber lining system), sometimes over 1/2in thick
- Exact condition of substrate unknown prior to removal of coating

Key Project Step: Surface Preparation



Project Step:

- Surface preparation performed using Sponge Blasting to minimize airborne particulates and to avoid utilizing a separate surface preparation method for end joint details

QC Documentation:

- All prepared concrete substrates achieved a minimum surface profile of ICRI CSP 3
- All substrates cleaned and dried prior to installation of CFRP system



Key Project Step: Surface Preparation



Project Step:

- CFRP lining system terminates into the steel substrate to ensure water tightness

QC Documentation:

- All prepared steel surfaces achieved a near white metal blast SP10 and a minimum surface roughness of 2 mils
- All substrates cleaned and dried prior to installation of CFRP system


Unique Project Challenges



- Extensive pitting and concrete patches observed on prepared substrate
- Additional details identified that were not shown on drawings
- Specialty detailing to accommodate thermowell was designed after construction began



Key Project Step: Mixing and Saturation



Project Steps:

- Materials arrive on site in premeasured containers for part A and B components
- Designated mixing region is an isolated area to avoid material contamination
- Mechanical saturator ensures consistent application of epoxy to carbon fiber

QC Documentation:

- Lot numbers of fabrics and epoxies are documented
- Gap between saturator rollers measured and calibrated using weigh test
- Weigh test verifies ratio of fabric to epoxy is within tolerance (1:1 for carbon fiber fabric, 0.8:1 for glass fiber fabric $\pm 10\%$)



Key Project Step: Adhesion Testing



Project Step:

- Surface preparation is verified by performing an adhesion test per ASTM D4541 on an adjacent section of prepared pipe

QC Documentation:

- A minimum of three (3) test pulls performed at three separate test regions
- Failure mode documented
- Minimum pull-off test of 200 psi required



Unique Project Challenges



Project required custom built two-tiered engineered scaffold for the following requirements:

- Live load of 25 psf
- 30 ft spans
- Changes in vertical slope midway through span
- Specialty connection designs required by PSEG safety dept
- All materials required to fit through limited access into the pipes

Key Project Step: End Joint Details



Project Steps:

- Epoxy mortar in joint region used to create a sloped transition for the CFRP
- Glass layer installed in direct contact with steel substrate to create a dielectric barrier between the CFRP and steel
- All layers of longitudinal and circumferential CFRP installed onto the main pipe are also installed into the joint

QC Documentation:

- Slope of epoxy mortar verified (2:1 slope)
- Air temperature, and surface temperature documented (min of 40°F)
- Humidity in pipe monitored (min of 5°F above dew point)

Key Project Step: CFRP Installation



Project Steps:

- Unidirectional mechanically saturated carbon fiber fabric installed in both longitudinal and circumferential directions
- CFRP design serves as stand alone system to resist 100psi internal pressure and - 14.7 psi vacuum pressure without reliance on host pipe

QC Documentation:

- Air temperature, surface temperature, and humidity during installation documented
- Alignment of CFRP layers observed (maximum of 5 degree misalignment)
- Minimum development length of 12in in fiber direction



Key Project Step: CFRP Final Cure



Project Step:

- After top coat is installed, final cure of CFRP system is performed at elevated temperature

QC Documentation:

- Air temperature, surface temperature, and humidity during CFRP cure recorded
- Shore D hardness values throughout pipe recorded to document progression of cure
- Degree of cure testing performed to verify degree of cure achieved for CFRP system

Key Project Step: CFRP Tensile Test Panels



Project Step:

- During each shift of CFRP installation, two test panels are fabricated

QC Documentation:

- Air temperature and humidity during CFRP test panel fabrication are recorded
- Lot numbers for carbon fiber fabric documented
- Once panels cure, they are sent off to 3rd party test facility for tensile tests per ASTM D3039

Key Project Step: Final Walkthrough



Project Step:

- After final cure is completed and scaffolding is removed, a final Quality walkthrough and FME check with all QA/QC personnel is performed

QC Documentation:

- Final walkthrough is signed off on by:
 - 3rd party Inspector
 - Structural QC Inspector
 - PSEG Engineering Team
 - PSEG System Owner